BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/03/2018-19 Dt: 01-12-2018

APPROVED TENDER SCHEDULE –'B'

Item No: 03

Name of Work:-Improvements and Construction of drains at Supreme layout (Vinivink Shastri layout) in ward No:01 of Yelahanka Sub division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Sri. Sri P RAVICHANDRA	
				Rate	Rate in Words
1	KSRB 2-1.1: Earth work in surface excavation in hard soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1,P. No. 5/ Item No. 2.2/ PWD SR 2016-17	Cum	330.75	263.94	Rupees Two Hundred Sixty Three and Paise Ninety Four Only
2	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 136 (SR 2018-19)	Cum	330.75	87.56	Rupees Eighty Seven and Paise Fifty Six Only
3	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3)/ PWD SR 2018-19	Cum	49.61	5408.12	Rupees Five Thousand Four Hundred Eight and Paise Twelve Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Sri. Sri P RAVICHANDRA	
				Rate	Rate in Words
	Providing and laying Plain /reinforced cement concrete for side drains wall and bottom thickness 15cm using M20 nominal mix concrete with OPC cement at 300kg with 20mm and down size granite metal coarse aggregate at 0.69 cum and fine aggregate at 0.43 cum machine mixed well compacted for walls at bottom including centring shuttering cost of materials HOM of machineries curing etc.completeexcluding cost of steel as per MORTH specification No.1500,1700,2200 Page No 271 Ite mo 37.59.2 SR 2018-19	Cum	122.45	7070.20	Rupees Seven Thousand Seventy and Paise Twenty Only
5	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. TMT bars Fe 500 KBS 4.6.3 Page No. 18/ Item No. 4.46/ PWD SR 2018-19	Tonne	7.58	75223.96	Rupees Seventy Five Thousand Two Hundred Twenty Three and Paise Ninety Six Only
6	RCC Precast covering slab for drain (10cm thick)	sqm	339.60	2100.00	Rupees Two Thousand One Hundred Only
7	Providing precast slab of 250 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc., complete as per the direction of engineer in charge-	sqm	28.08	5111.00	Rupees Five Thousand One Hundred Eleven Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.